INDIRA GANDHI NATIONAL OPEN UNIVERSITY
CONSTRUCTION & MAINTENANCE DIVISION
MAIDAN GARHI, NEW DELHI- 110 068
NOTICE RE-INVITING QUOTATION

No. IG/CMD/EE(C)/NIQ/2017-18/
Dated: 04.10.2017

The Executive Engineer (C) Construction & Maintenance Division re-invite on behalf of Vice-Chancellor, Indira Gandhi National Open University, sealed item rate quotations for the following work from the registered contractors of CPWD/MES/BRO/MCD/PWD/DDA or any other Govt./Autonomous body or specialized agency. Who have already executed at least one similar work costing 80% or two similar works costing 60% each or three similar works costing 40% each of estimated cost during the last seven years for any Govt. department. The quotations will be issued only on production of Original PAN No., Registered GST No., latest return file GSTN and proof for satisfactory completion of similar work duly certified by the competent authority of the client department.

S.no	Name of work	Estimated cost	Earnest money	Last date of Issue of quotation	Date of opening of quotation	Time allowed
1.	P/F G.I. pipe line for VIP Guest House, V.C office, Block no.-16, 17 & CMD office.	1,99,588/-	4,990/-	11.10.2017	13.10.2017	01Month

Quotation forms and conditions can be obtained from the office of the undersigned Indira Gandhi National Open University, Construction & Maintenance Division, Maidan Garhi on any working day up-to 2:30 PM on the date given above. The time for submission of quotations are up-to 3:00 PM which shall be opened on the same day at 3:30 PM on the date given above. The undersigned reserves the right to accept or reject any quotations without assigning any reason.

Note:- The quotation documents in the website are for information only. Downloaded quotation documents will not be considered for bidding. The contractor shall quote their rates in the NIQ issued by the department only. If rates quoted in other form will not be considered. Contractors/Agencies have to act as per above NIQ.

(Raj Pal Singh)
Executive Engineer (C)i/c

Name of work: - P/F G.I. pipe line for VIP Guest House, V.C office, Block no.- 16, 17 & CMD office

SPECIFICATION & SPECIAL CONDITIONS OF CONTRACT:

1. Unless otherwise specified the work shall be carried out in accordance with the printed CPWD specification 1977 for the works at Delhi correction slips issued till the date of opening of tenders/quotation. In the event of any dispute the followings shall be the order of priority to decide the issue:-
    a. Nomenclature of item read with special conditions of the contract and general specifications
    b. CPWD specifications
    c. ISI specifications
    d. Instructions of Engineer In charge.

2. Before quoting the contract shall inspect the site of work and shall fully acquaint him self about the conditions with regard to accessibility of site required for the satisfactory execution of work. No claim whatsoever shall be entertained by the department on this account.

3. The quantities shown in the schedule are tentative and may change as per site conditions. The Contractor shall not claim anything extra on this account. The payment shall be made as per actual quantities of work done and as per the conditions of the contract.

4. The work executed under the contract shall be subject to inspection carried out by the departmental officers. Any defects regarding workmanship or quality of material to be used as pointed out during or after completion of work by the departmental officers shall have to be rectified by the contractor at his own cost and risk, and in case the contractor fails to do so, it will be got rectified by the department at the risk and cost of the Contractor.

5. All precautionary measures should be adopted for the safety purposes for any accident during the execution of work occurring at site, the contractor shall be overall responsible for the same.

6. Water if available shall be supplied to the contractor and 1% on account of water charges shall be recovered from him on the gross amount of work done. However, if the electricity is required for work, the same shall be provided to the contractor and .0.25% on account of electricity charges shall be recovered from him on the gross amount of work done.

7. The Contractor shall put Rubber stamp comprising name of Agency, Address, and Telephone No.s and signature on all relevant papers and conditions of the Quotation, in token of acceptance, failing which the quotation submitted by the Agency will be summarily rejected.

8. After the award of work, if the agency fails to start the work the earnest money and performance guarantee submitted by them will be 100% forfeited and the agency will be debarred for a period of three years to quote tender/quotation for IGNOU works.

Executive Engineer (C)i/c

SCHEDULE OF QUANTITY

Estimate Cost :- 1,99,588/-
Ernest Money:- 4,990/- (P.O in favour of IGNOU) **Issued to:-**
Time allowed:- 1 Month **Date of opening:-**

Name of work:- P/F G.I. pipe line for VIP Guest House, V.C office, Block no.-16, 17 & CMD office.

S.no	Description	Qty	Unit	Rate	Amount
1.	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means over areas (exceeding 30cm in depth. 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth, lead upto 50m and lift upto 1.5m, and directed by engineer-in-charge. a. All kinds of soil	16cum	Cum		
2.	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level in all shapes and sizes in a. Cement mortar 1:6 (1 cement : 6 coarse sand)	1.63 cum	Cum		
3.	Reinforced cement concrete work in walls (any thickness), including attached pilasters, buttresses, plinth and string courses, fillets, columns, pillars, piers, abutments, posts and struts etc. above plinth level up to floor five level, excluding cost of centering, shuttering, finishing and reinforcement a. 1:1.5:3 (1 cement : 1.5 coarse sand (Zone-III) : 3 graded stone aggregate 20 mm nominal size)	0.48 cum	Cum		
4.	Providing and fixing G.I. pipes complete with G.I. fittings including trenching and refilling etc. External work a. 20 mm dia nominal bore b. 32 mm dia nominal bore	 146.15 213	 Mtr. Mtr.		
5.	Providing and fixing gun metal gate valve with C.I. wheel of approved quality (screwed end) a. 20 mm nominal bore b. 32 mm nominal bore.	 04 no. 04 no.	 Each Each		
6.	Providing and placing on terrace (at all floor levels) polyethylene water storage tank, IS 12701 marked, with cover and suitable locking arrangement and making necessary holes for inlet, outlet and overflow pipes but without fittings and the base support for tank. a. Circular tank	14000 Ltr.	P/ltr.		

(Raj Pal Singh)
Executive Engineer (C)i/c