INDIRA GANDHI NATIONAL OPEN UNIVERSITY
CONSTRUCTION AND MAINTENANCE DIVISION
MAIDAN GARHI, NEW DELHI-110068
NOTICE INVITING QUOTATION

No. IG/CMD/EE(C)/NIQ/2018-19/515
Dated: 26.07.2018

The Executive Engineer (C) Construction & Maintenance Division invite on behalf of Vice-Chancellor, Indira Gandhi National Open University, sealed item rate quotations for the following work from the registered contractors of CPWD/MES/BRO/MCD/PWD/DDA or any other Govt./Autonomous body. Who have already executed at least one similar work costing 80% or two similar works costing 60% each or three similar works costing 40% each of estimated cost during the last seven years for any Govt. department. The quotations will be issued only on production of Original GSTIN No. and PAN No. proof for satisfactory completion of similar work duly certified by the competent authority of the client department.

S. No.	Name of work	Estimated cost	Earnest money	Last date of Issue of quotation	Date of opening of quotation	Time allowed
1.	Cleaning of storm water drain at IGNOU Down Campus.	50,442/-	1,261/-	06.08.2018	08.08.2018	10 Days

Quotation forms and conditions can be obtained from the office of the undersigned Indira Gandhi National Open University, Construction & Maintenance Division, Maidan Garhi on any working day up-to 2:30 PM on the date given above. The time for submission of quotations are up-to 3:00 PM which shall be opened on the same day at 3:30 PM on the date given above. The undersigned reserves the right to accept or reject any quotations without assigning any reason.

Note:- The quotation documents in the website are for information only. Downloaded quotation documents will not be considered for bidding. The contractor shall quote their rates in the NIQ issued by the department only. If rates quoted in other form will not be considered. Contractors/Agencies have to act as per above NIQ.

Executive Engineer (C)

Name of work:- Cleaning of storm water drain at IGNOU Down Campus.

SPECIFICATION & SPECIAL CONDITIONS OF CONTRACT:

1. Unless otherwise specified the work shall be carried out in accordance with the printed CPWD specification 2009 for the works at Delhi correction slips issued till the date of opening of tenders/quotation. In the event of any dispute the followings shall be the order of priority to decide the issue:-
    a. Nomenclature of item read with special conditions of the contract and general specifications
    b. CPWD specifications
    c. ISI specifications
    d. Instructions of Engineer In charge.

2. Before quoting the contract shall inspect the site of work and shall fully acquaint himself about the conditions with regard to accessibility of site required for the satisfactory execution of work. No claim whatsoever shall be entertained by the department on this account.

3. The quantities shown in the schedule are tentative and may change as per site conditions. The Contractor shall not claim anything extra on this account. The payment shall be made as per actual quantities of work done and as per the conditions of the contract.

4. The work executed under the contract shall be subject to inspection carried out by the departmental officers. Any defects regarding workmanship or quality of material to be used as pointed out during or after completion of work by the departmental officers shall have to be rectified by the contractor at his own cost and risk, and in case the contractor fails to do so, it will be got rectified by the department at the risk and cost of the Contractor.

5. All precautionary measures should be adopted for the safety purposes for any accident during the execution of work occurring at site, the contractor shall be overall responsible for the same.

6. Water if available shall be supplied to the contractor and 1% on account of water charges shall be recovered from him on the gross amount of work done. However, if the electricity is required for the work, the same shall be provided to the contractor and .0.25% on account of electricity charges shall be recovered from him on the gross amount of work done.

7. After the award of work, if the agency fails to start the work the earnest money and performance guarantee submitted by them will be 100% forfeited and the agency will be debarred for a period of three years to quote tender/quotation for IGNOU works.

8. Cleaning of storm water drain will be carried out in a mechanized manner.

9. No manual scavenging to be done.

10. The proper disposal of silt/sludge is in the scope of contractor and to be done immediately after removal from the drain.

11. The rates are inclusive of G.S.T., taxes, cess etc. and nothing will be paid extra. Deductions of admissible taxes will be made by university.

Executive Engineer (C)

SCHEDULE OF QUANTITY

Estimated cost :- 50,442 /- **Issued to:-**

Earnest Money :- 1,261 /- (P.O. in favour of IGNOU) **Date of opening:-**

Time allow :- 10 Days

Name of work:- Cleaning of storm water drain at IGNOU Down Campus.

S. No.	Description	Qty.	Unit	Rate	Amount
1.	Cleaning of storm water drain/sump/pits by hiring of 9000 liters tank capacity BS-IV chasis mounted high suction machine having 130 HP engine. The machine will be deployed with suction motor with 4 inch hose pipe, operators, supervisors and driver etc. complete to the entire satisfaction of Engineer-in-charge.	02 Job	Per Day (8 hours)		
2.	Cleaning of storm water drain and supply of labour with T and P for lifting malba/desilting from storm water drain within lead of 50 meters to the entire satisfaction of Engineer-in-charge.	12	Each		
3.	Disposal of building rubbish/malba/similar unserviceable, dismantled or waste materials by mechanical means, including loading, transporting, unloading to approved municipal dumping ground or as approved by Engineer-in-charge, beyond 50 m initial lead, for all leads including all lifts involved.	10	Cum		

Executive Engineer (C)